

## CT Green Roof Components - 02/18

PRODUCT	LIST	SIZE	AREA	NOTES
Separation Fabric SD (4 oz)	\$80.00	6 ft x 100 ft	600 ft2	G systems
Separation Fabric HD (6 oz)	\$116.00	6 ft x 100 ft	600 ft2	P systems
Protection Mat SD (10 oz)	\$144.00	6 ft x 100 ft	600 ft2	P systems
Protection Mat HD (16 oz)	\$148.00	6 ft x 67 ft	400 ft2	P systems
Protection Mesh	\$360.00	6 ft x 150 ft	900 ft2	inverted roofs, storage roofs
Capillary Mat	\$244.00	6 ft x 50 ft	300 ft2	G systems, CT Modular
Water Storage Mat	\$172.00	6 ft x 33 ft	200 ft2	G or P systems, blue roofs
Drainage Mat LF	\$272.00	6 ft x 33 ft	200 ft2	M systems (slopes)
Capillary Drainage Mat	\$436.00	6 ft x 33 ft	200 ft2	M systems (slopes)
Reinforcing Mesh	\$240.00	6 ft x 150 ft	900 ft2	wind reinforcing
Root Barrier, 30 mil LLDPE	\$272.00	10 ft x 50 ft	500 ft2	slopes less than 1:12
Root Barrier Tape	\$14.80	3/4" x 50 ft	-	1+ foot per lineal foot of root barrier
DrainPlate HS (1"), half sheet	\$13.80	39" x 39"	10.6 ft2	P systems, maximum strength
DrainPlate HS (1")	\$25.60	39" x 79"	21.5 ft2	P systems, maximum strength
DrainPlate HP (1.5")	\$35.60	39" x 79"	21.5 ft2	P systems, maximum flow, high storage
DrainPlate HV (2.5")	\$48.00	39" x 79"	21.5 ft2	P systems, maximum storage
FlexDrain	\$150.00	6 ft x 50 ft	300 ft2	inverted G systems, CT Modular
Drainage Conduit, triangular	\$4.80	39"	-	G systems
Drainage Conduit Tee, triangular	\$4.12	-	-	G systems
Drain Box, top + bottom + 4" sidewall	\$76.00		-	
Drain Box Sidewall, 4"	\$36.00		-	order one per additional 4" height
Drainage Conduit, semi-circular	\$7.20	39"	-	G systems
X-Box, 2"	\$16.80	23.75" x 23.75"	4 ft2	limited availability
X-Box, 4"	\$18.80	23.75" x 23.75"	4 ft2	
X-Box, 6"	\$26.20	23.75" x 23.75"	4 ft2	
X-Box, 8"	\$33.60	23.75" x 23.75"	4 ft2	limited availability
X-Box, 12"	\$46.80	23.75" x 23.75"	4 ft2	limited availability
X-Box, 24"	\$92.40	23.75" x 23.75"	4 ft2	limited availability
X-Box Dovetail Connector	\$0.48			four for each X-Box
X-Box Stacking Pin	\$0.48			
Aluminum Edge, 3"	\$40.00	72"	-	for modular tray system
Aluminum Edge, 4"	\$44.00	72"	-	brace every 3 ft if unbalanced load

<b>Aluminum Edge, 6"</b>	\$52.00	72"	-	brace every 3 ft if unbalanced load
<b>Aluminum Edge, 8"</b>	\$64.00	72"	-	brace every 2-3 ft if unbalanced load
<b>Aluminum Edge, 12"</b>	\$96.00	72"	-	brace every 2 ft if unbalanced load
<b>Aluminum Edge Connector, 3"</b>	\$5.80	7"	-	one for each edge and corner
<b>Aluminum Edge Connector, 4"</b>	\$6.40	7"	-	one for each edge and corner
<b>Aluminum Edge Connector, 6"</b>	\$7.20	7"	-	one for each edge and corner
<b>Aluminum Edge Connector, 8"</b>	\$8.40	7"	-	one for each edge and corner
<b>Aluminum Edge Connector, 12"</b>	\$13.40	7"	-	one for each edge and corner
<b>Aluminum Interior-Flange Corner, 3"</b>	\$36.00	12"x12"	-	always use if unbalanced loads
<b>Aluminum Interior-Flange Corner, 4"</b>	\$40.00	12"x12"	-	always use if unbalanced loads
<b>Aluminum Interior-Flange Corner, 6"</b>	\$44.00	16"x16"	-	always use if unbalanced loads
<b>Aluminum Interior-Flange Corner, 8"</b>	\$48.00	16"x16"	-	always use if unbalanced loads
<b>Aluminum Interior-Flange Corner, 12"</b>	\$80.00	18"x18"	-	always use if unbalanced loads
<b>Aluminum Exterior-Flange Corner, 3"</b>	\$44.00	12"x12"	-	always use if unbalanced loads
<b>Aluminum Exterior-Flange Corner, 4"</b>	\$48.00	12"x12"	-	always use if unbalanced loads
<b>Aluminum Exterior-Flange Corner, 6"</b>	\$52.00	12"x12"	-	always use if unbalanced loads
<b>Aluminum Exterior-Flange Corner, 8"</b>	\$60.00	12"x12"	-	always use if unbalanced loads
<b>Aluminum Exterior-Flange Corner, 12"</b>	\$116.00	18"x18"	-	always use if unbalanced loads
<b>Aluminum Brace, 4"</b>	\$11.40	4"x6"	-	use for sloped roofs or unbalanced loads
<b>Aluminum Brace, 6"</b>	\$12.60	6"x8"	-	use for sloped roofs or unbalanced loads
<b>Aluminum Brace, 8"</b>	\$13.80	8"x12"	-	use for sloped roofs or unbalanced loads
<b>Aluminum Brace, 12"</b>	\$19.60	12"x15"	-	use for sloped roofs or unbalanced loads
<b>Drip Tubing, 1/4 gph, 12" oc</b>	\$124.00	500 ft		for P systems, 12" oc
<b>Drip Tubing, 1/4 gph, 18" oc</b>	\$124.00	500 ft		for modular systems, every second tray
<b>Drip Tubing, solid</b>	\$24.00	250 ft		for headers
<b>Drip Tee</b>	\$8.40	25		
<b>Drip Elbow</b>	\$8.20	25		
<b>Shutoff Valve</b>	\$3.20	1		
<b>Fertilizer, 10 lbs</b>	\$36.00	1 gallon pail	3000 ft2	apply spring and summer